

# CONSIDERATIONS IN THE DESIGN OF THREE PHASE COMPACT TRANSMISSION LINES

by

Thomas J. F. Ordon, PE  
Senior Member IEEE  
Consultant  
Skaneateles, NY

and

Keith E. Lindsey, Ph.D.  
Senior Member IEEE  
Lindsey Manufacturing Company  
Azusa, CA

## Abstract

Recent concerns of the public about possible health effects of magnetic fields has resulted in an increased emphasis on the use of compact transmission lines as a means of managing (ie. reducing) magnetic fields. This paper examines how one utility, Niagara Mohawk Power Corporation, investigated 115kV compact transmission configurations and used a full scale prototype to determine the impact of the proposed design on work practices.

## Introduction

In 1988, Niagara Mohawk Power Corporation approved funding for the *Maximum Power Transfer Project*. It would identify and demonstrate field management technologies and would formulate a strategy to strengthen Niagara Mohawk's power delivery capability at the lowest cost to its customers. The project would respond to concerns within the Company that stringent field limits might be imposed by government regulators in response to the public's outcry concerning possible health effects from fields. Such limits would severely restrict transfers on the Company's transmission system and would result in higher costs for wider rights-of-way, or, require decreased power ratings for existing (or future) lines.

The project would also respond to those critics who identified magnetic fields and health concerns during the siting and approval of new electric facilities. The Company needed to construct and operate new facilities in order to maintain an efficient electric transmission system. Government regulators, lacking any scientific basis for establishing regulations defining safe magnetic field levels had prompted utilities including Niagara Mohawk to take steps to identify field management techniques as a reasonable step in dealing with public concerns<sup>1</sup>.

In addition, utility workers who came in close proximity to electric facilities on a regular basis were concerned about the safety of their working environment. This project would provide information on field behavior in the vicinity of transmission facilities and identify the design innovations that would make field management possible.

## Background

Niagara Mohawk's study investigated designs which could be used for the construction of new 115kV overhead electric transmission systems with lower ground level fields than the Company's conventional horizontal design. It was proposed to develop a structure which could be constructed with existing materials and experience and which could be put into service in a relatively short time at the lowest additional cost.




Figure 1  
Proposed Design Compared with Niagara Mohawk's Standard Design

The study<sup>2</sup> recommended the following design:

- a compact inverted delta phase arrangement with a phase to phase conductor spacing of 6 feet 4 inches (Figure 1)
- magnetic fields produced by the new design would be 25% of the magnetic fields produced by the standard horizontal design at both normal design load and at maximum allowable design load,
- radio noise levels generated would be 5 to 10 dB higher than those of the standard design
- audible noise levels would be negligible
- in-span spacers would be used to prevent flashovers due to ice dropping or galloping



A more detailed discussion of loadings, mechanical reactions and hardware selection for compact lines can be found in "Practical Aspects of Hardware for Compact Lines".<sup>3</sup>

### Design Review

It is a Niagara Mohawk requirement to have the Company's Hot Stick Committee review any new structural system or structure if that system or structure would eventually be recommended as a system approved standard. The Committee consists of supervisory personnel from the Operating, Safety, and Training Departments. Members of the Committee would also examine the work procedures necessary when performing maintenance on the structure and how existing work practices were affected.

The Committee determined very early in the project that their review could not be accomplished by examining drawings or specifications. In order to determine if the configuration could be installed, maintained and operated in accordance with Niagara Mohawk work practices, it was agreed that a prototype of the structure should be erected. This would permit the Committee to examine the design and test various work procedures in full scale, life size circumstances. Committee members concentrated specifically on confirming that required working clearances were maintained and that individual conductor support insulators could be replaced using hot-stick techniques.




Figure 2  
Structure Prototype Erected for Testing at the Test Site

Following completion of the detailed design of the tangent structure, materials were ordered and a prototype of the proposed design (Figure 2) was erected at a test site. A section of line consisting of three spans simulated actual conditions. The test line was not energized. The Hot Stick Committee verified the adequacy of the working clearances between the poles and the crossarm and the conductors, and determined how linemen could access the structure to work on the conductor hardware assembly. The Committee concluded that personnel should be able to work from the crossarm and that the use of support platforms would facilitate

working from the poles. In order to permit these procedures and maintain required working distances between energized components and a worker on the structure, it was necessary to increase the spacing between the wood poles and the spacing between the crossarm and the conductor support assembly. The changes recommended were:

- increasing pole separation from 16 feet to 19 feet 6 inches
- increasing spacing between the crossarm and the conductors from 5 feet to 11 feet 2 inches

The prototype at the site was modified to incorporate these changes (Figure 3).




Figure 3  
Modified Prototype




Figure 4  
Removing the Inner Insulators in the "U" String

The Hot Stick Committee investigated how insulator assemblies could be replaced using hot-stick techniques. It was demonstrated and confirmed by actually performing the procedure that the outer string in the "U", the inner string of the "U" (Figure 4) and, finally, the insulators in the "V" (Figure 5) could be successfully removed and re-installed using hot sticks.




Figure 5  
Removing the Insulators in the "V" String

The Committee also examined the in-span spacers (Figure 6). Three (3) individual polymer interphase spacers were used at a span location. A tool which can be operated with a hot stick and which will reduce the forces on any one interphase spacer and facilitate its removal and installation is being developed. A prototype of the tool was successfully demonstrated.




Figure 6  
In-Span Interphase Spacers

The Hot Stick Committee employed one Company line truck with a bucket and the Company Hot-stick trailer to perform their investigation at the test site.

Following the work of the Hot Stick Committee and a review of the results, the design of the structure was finalized and drawings and a bill of material were prepared.

The structure has been used as part of a new 115kV project north of Syracuse, NY.<sup>4</sup> Its performance is being monitored. Niagara Mohawk is now working to develop angle and strain structures for the low EMF 115kV family of structures.

## Conclusions

The following conclusions resulted from this project:

- a full scale prototype of a proposed structure is an ideal way for a utility to identify and investigate proposed work practices
- reduced work-space and the complex reactions to forces acting on a "U" string requires careful attention to work procedures
- standard conductor hardware does lend itself for use in compact conductor configurations, for example, special yoke plates and suspension clamps are required for use in a "U" string

The development of the low EMF structure by Niagara Mohawk is an evolutionary process. The work that I have described demonstrates how Niagara Mohawk addressed the task of determining how the use of a new and non-standard conductor support system should be evaluated to determine compliance with the Company's work rules.

## References

1. Orden, Thomas J. F., "A Utility Perspective on Factors Driving Line Compaction", 13th IEEE/PES Transmission and Distribution Conference and Exposition, Chicago, Illinois, April 10-15, 1994
2. Stewart, James R. and Douglas, Dale A., "Development of a Low EMF Structure for the Schodack 115kV Tap Line Project for Niagara Mohawk Power Corporation", (Report), Power Technologies, Inc., June 25, 1992
3. Lindsey, Dr. Keith E., "Practical Aspects of Hardware for Compact Lines", 13th IEEE/PES Transmission and Distribution Conference and Exposition, Chicago, Illinois, April 10-15, 1994
4. Orden, Thomas J. F., "Maximum Power Transfer, (Project 88-9429), 115kV Inverted Delta Structure", (Report), Niagara Mohawk Power Corporation, February 16, 1994